

**BOP STACK**

**3-1/16" 10M QUAD BOP**

**OVER 3500PSI**

10M Side Door Packer

**BOP Shear Rams Capable of Shearing any Coiled Tubing up to 1-1/2" Ran Across Them at or below MAOP**

Kill Line  
One 2" Full Bore 10M Manual Valve and One 2" 10M Hydraulic Valve

<b>3-1/16" 10 M Quad BOP</b>
Hydraulically-operated Blind rams
Hydraulically-operated shear rams
<b>Kill Line</b>
Hydraulically-operated slip rams
Hydraulically-operated pipe rams

3-1/16" 10M Pipe Ram  
Hydraulically-operated

Choke Line  
One 2" Full Bore 10M Manual Valve and One 2" 10M Hydraulic Valve

Optional 3-1/16" 10m Spacer Spool(s)

3-1/16" 15M X 3-1/16" 10M Flange

**BOP BLIND/SHEAR Rams Capable of Shearing any Coiled Tubing up to 1-1/2" Ran Across Them at or below MAOP**

3-1/16" 15M X 3-1/16" 10M Flange

3-1/16" 15M Hydraulically-operated Blind/Shear ram

With One 2X1 10M Halco Valve and one 10M Check Valve on Outlet For Testing

3-1/16" 10M Rental Gate Valve

Tree Crown Valve

